



## Ocean County Board of Commissioners

OFFICE OF THE  
OCEAN COUNTY COMMISSIONERS

Director Joseph H. Vicari  
Deputy Director Gary Quinn  
Commissioner Barbara Jo Crea  
Commissioner Virginia E. Haines  
Commissioner John P. Kelly

101 Hooper Avenue  
Toms River, New Jersey  
08754-2191  
(732)929-2005  
(732)505-1918

### Board Meeting Agenda

Date: October 4, 2023 - 4:00 PM  
Location: Administration Building  
Room 119  
101 Hooper Avenue  
Toms River, NJ 08754

Agenda: Awarding a Contract for the furnishing and delivery of DEBRIS LOADER to Granturk Equipment Co., Inc., the sole qualified bidder. (B2023-165)

<b>Official Resolution#</b>		<b>2023001411</b>					
Meeting Date		10/04/2023					
Introduced Date		10/04/2023					
Adopted Date		10/04/2023					
Agenda Item		k-4					
CAF #							
Purchase Req. #		B2023-165					
Result		Adopted					
COUNTY COMMISSIONER	PRES.	ABS.	MOVE	SEC	AYE	NAY	ABST.
Vicari	✓				✓		
Quinn	✓				✓		
Crea	✓			✓	✓		
Haines	✓				✓		
Kelly	✓		✓		✓		

I HEREBY CERTIFY THAT THIS DOCUMENT IS A TRUE, COMPLETE AND ACCURATE COPY OF THIS RESOLUTION, ADOPTED BY OCEAN COUNTY BOARD OF COMMISSIONERS, NJ AT THE MEETING REFERENCED THEREON

*Michelle I. Gunther*

---

Clerk Of The Board

CONTRACT NO. MUST BE ON ALL  
PAPERS, DOCUMENTS, INVOICES, VOUCHERS  
NO. B2023-165

RESOLUTION

October 4, 2023

WHEREAS, on September 6, 2023, pursuant to legal advertisements therefor, sealed bids were received for the furnishing and delivery of DEBRIS LOADER for the County of Ocean; and

WHEREAS, at the advertised time, one response was received from the following bidder:

<u>Name of Bidder</u>	<u>Address of Bidder</u>
Granturk Equipment Co., Inc.	One Schuylkill Parkway Bridgeport, PA 19405 (610) 239-9800

; and

WHEREAS, after the receipt and examination of same, the County Purchasing Agent has now recommended to this Board that the sole qualified bid, according to specifications, namely that of, GRANTURK EQUIPMENT CO., INC. be accepted.

NOW, THEREFORE, BE IT RESOLVED by the BOARD OF COMMISSIONERS of the COUNTY OF OCEAN, STATE OF NEW JERSEY, as follows:

1. The Director and Clerk of this Board are hereby authorized and directed to enter into a contract for the furnishing and delivery of DEBRIS LOADER for the County of Ocean, for the contract period from date of award through October 3, 2024, a period of one (1) year or until delivery is complete unless otherwise stated. The County reserves the right to extend the term of the contract pursuant to N.J.S.A. 40A:11-15, as follows:

A. GRANTURK EQUIPMENT CO., INC. for two (2) items, to wit:

ITEM NOS. 1 and 1A

For a Total Lump Sum Amount (Item Nos. 1 – 1A) of \$205,018.00.

This vendor has extended this contract to County Cooperative Contract System Participants.

2. Payments for the equipment and services to be acquired by this contract shall be made upon the approval of vouchers submitted by the successful bidders in accordance with the requirements of the Board of Commissioners and subject to the Board of Commissioners customary procedures. Delivery shall be made upon receipt of a Purchase Order issued by the Ocean County Department of Purchase, upon which delivery locations and needed quantities shall be indicated.

3. Funds for the equipment and services shall be available within the following funding Source: Parks Department O.E.

4. The contract number must be placed on all papers, documents, invoices and vouchers pertaining to said contract, the number being B2023-165.

5. BE IT FURTHER RESOLVED that certified copies of this Resolution shall be made available to the County Auditor, County Department of Purchasing, Department of Finance, Parks Department and Granturk Equipment Co., Inc., the successful bidder.

GRANTURK EQUIPMENT CO., INC.

PROPOSAL DOCUMENT REPORT  
 Bid No. TBD  
 DEBRIS LOADER

Bidder also understands that only one (1) bid submission shall be considered. Please DO NOT Submit a manual bid response. Submitting a manual response in addition to the electronic response is cause for rejection of your bid.  
 Confirmed

PRICE TABLES  
 DEBRIS LOADER

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total	Mfr. Make/Model:	Warranty Details:
1	Model Year 2023, or Newer, Monster Model MPE-1M-20CUYD 74 JD Wheel Style Debris Loader, As Specified or Equal	2	EA	\$99,259.00	\$198,518.00		
1A	Top Mounted Debris Deflector, As Specified	2	EA	\$3,250.00	\$6,500.00		
<b>TOTAL</b>					<b>\$205,018.00</b>		



## COMPLIANCE PAGES – DEBRIS LOADER

Page 1 of 4

✓ **ITEM # 1 - MODEL YEAR 2023, OR NEWER, MONSTER MODEL MPE-TM-20CuYd 74 JD WHEEL STYLE DEBRIS LOADER, AS SPECIFIED**

DESCRIPTION	COMPLIANCE	
	YES	NO
Model Year 2023, or Newer, Monster Model MPE-TM-20CuYd 74 JD Wheel Style Debris Loader, As Specified or Equal	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Manufacturer/Model - Monster MPE-TM Wheel Style Debris Loader	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Warranty - Standard 2 year warranty on base unit, including everything minus engine, 2 year/2000 hour warranty on engine	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Delivery, A.R.O. - Delivery to Atlantis Golf Course, Little Egg Harbor, NJ	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Engine:</b>		
74HP John Deere 4045T 4 cylinder Tier 4 Turbo diesel engine.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Oversized heavy duty trash style radiator with 6 bladed cooling fan.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Engine fully enclosed with a high flow shroud design to protect engine while maintaining cooling requirements.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Integral 2 stage hinged front radiator screen for cleaning while engine is running.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Fully digital display for monitoring engine functions, including high temp/low pressure shut down system with pre shut down audible warning.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Equipped with emergency stop button and keyed ignition switch.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Engine Power Take Off</b>		
Heavy duty hand operated cam over locking style with an 1 1/2" clutch and a minimum 1-1/4" shaft supported by two internal roller bearings.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Engine Base</b>		
Unitized design and constructed of 7 gauge steel.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Fuel Tank</b>		
12 gauge steel with two (2) internal baffles, extended filler neck, tethered cap and sight gauge. 36 gallon capacity, mounted fully enclosed in the engine base for safety.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Four (4) blades, no less than 3/4" thick with shredding serrations and a full backing plate, no less than 5/16" thick. 4" diameter center hub, fully gusseted.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Impeller to be 100% fully welded and balanced. Outside diameter, 29-1/2".	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Impeller Housing</b>		
31" diameter and 12" in width. 7 gauge steel with accessible internal replaceable liners held in place with twelve (12) heat-treated alloy flat head bolts and hardware.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Maximum clearance between hosing and impeller not to exceed 1/2".	<input checked="" type="checkbox"/>	<input type="checkbox"/>

**ITEM # 1 - MODEL YEAR 2023, OR NEWER, MONSTER MODEL MPE-TM-20CuYd 74 JD  
WHEEL STYLE DEBRIS LOADER, AS SPECIFIED (CONT'D)**

	<b>COMPLIANCE</b>	
	<b>YES</b>	<b>NO</b>
<b>DESCRIPTION (CONT'D)</b>		
<b>Performance</b>		
Capable of producing 22,000 CFM.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Intake Hose and Nozzle</b>		
Located on curb side of unit. 18" in diameter, 10' in length. Heavy duty wire reinforced flexible rubber. Intake nozzle constructed of 16 gauge steel with a 1" round handle.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Hose Boom</b>		
Spring loaded and pivots on two (2) 1-1/2" flange bearings. Constructed of 1-1/2" x 3" structural tube, 6' in length.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Debris Discharge Section</b>		
Mounted directly over the impeller housing. 12" square with replaceable 1/4" steel liner in the 90 degree elbow section held in place with four (4) heat treated alloy flat head bolts with lock washers and hex nuts.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Trailer Frame, Axels, Tires and Wheels</b>		
Trailer frame constructed of 3" x 8" x 1/4" wall structural tubing and 1/4" steel plate.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Trailer is to have a height adjustable lunette ring hitch with a capacity of 35,000 lbs.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Dual Dexter D12000 axles with dual wheel style hubs, slipper style leaf springs, oil bath bearings and load leveling rockers.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Axles are to be equipped with electric brake and breakaway system.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
GVW 24,000 Lbs	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Total of eight (8) tires, four (4) per axle, 12 ply rating.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Tire size, 900 x 14.5 with a 14.5" x 7" steel dual wheel rim. <small>TIRE SIZE HAS CHANGED TO 235/80R16E</small>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Single 3" x 20" hydraulic cylinder for a front lifting jack and parking stand. Controlled by a 12 volt over hydraulic power unit with manual hand valve. Jack can function with engine off.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Debris Box</b>		
20 CuYd capacity.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Dimensions- 96" wide, 78" high, 139" long.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Lower section, unitized design of 10 gauge and 1/4" steel plate.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Upper section, unitized design of 13 gauge steel with a 10 gauge formed channel outer frame.	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Introduced on: October 4, 2023  
 Adopted on: October 4, 2023  
 Official Resolution#: 2023001411



**ITEM # 1 - MODEL YEAR 2023, OR NEWER, MONSTER MODEL MPE-TM-20CuYd 74 JD WHEEL STYLE DEBRIS LOADER, AS SPECIFIED (CONT'D)**

DESCRIPTION (CONT'D)	COMPLIANCE	
	YES	NO
<b>Debris Box (Cont'd)</b>		
Fully vented top with one removable screen panel of 1/4"-20 expanded mesh metal in a channel frame.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Two (2) box style rear doors, side hinged with three (3) heavy-duty strap style hinges on each door with one (1) cam style door lock per door.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Hold back chains on each door.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Lighting</b>		
All DOT required lighting, clearance, stop, turn and tail will be LED.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
7 way RV style light plug installed.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Four (4) oval shaped rear facing flush mounted sequential strobe lights with a switch mounted in engine control panel.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Hydraulics</b>		
Heavy duty self-contained 12 volt electric over hydraulic power unit with a manual two handle valve. This unit controls both the front trailer jack cylinder and the dumping mechanism. All hydraulic components rated at 300 PSI.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Dumping Mechanism</b>		
Crysteel LoBoy 24 ton scissor type hoist model F-18 located under the hopper. Controlled by a 12 volt over hydraulic power unit with manual hand valve. Box can dump with engine off.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Finish</b>		
Hunter green.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Initial Training</b>		
Initial training to take place at the Atlantis Golf Course, 261 Country Club Blvd, Little Egg Harbor, NJ. Shall include instruction on full operation of unit, including all safety related functions. Shall be conducted by a factory authorized representative. Training session will be four (4) hours long, spent with operators (standard operation training) and mechanic (service and repair training).	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Coordination of Training shall be made by the Parks department and shall take place no more than five (5) days after acceptance of the equipment.	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Introduced on: October 4, 2023  
 Adopted on: October 4, 2023  
 Official Resolution#: 2023001411

COMPLIANCE PAGES – DEBRIS LOADER

**ITEM # 1 - MODEL YEAR 2023, OR NEWER, MONSTER MODEL MPE-TM-20CuYd 74 JD WHEEL STYLE DEBRIS LOADER, AS SPECIFIED (CONT'D)**

DESCRIPTION (CONT'D)	COMPLIANCE	
	YES	NO
<b>Accessories</b>		
Shall include one (1) extra set of all applicable filters, including but not limited to, oil, air, fuel and hydraulic filters. Shall include one (1) extra set of all belts.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
One (1) fire extinguisher mounted to the machine on control side.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Three (3) sets of keys.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
One (1) Parts Manual.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
One (1) Service Manual.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Spare Tire and Rim.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>Options</b>		
1A. Top Mounted Debris Deflector	<input checked="" type="checkbox"/>	<input type="checkbox"/>