



JENNIFER L. BOWENS
PURCHASING AGENT

COUNTY OF OCEAN
DEPARTMENT OF PURCHASE
P.O. BOX 2191 ★ ADMINISTRATION BUILDING
TOMS RIVER, NEW JERSEY 08754-2191

Phone: (732) 929-2101
Fax: (732) 288-7636

SEPTEMBER 25, 2020

ADDENDUM NO. 1

CULVERT AND CART PATH REPAIR AT ATLANTIS GOLF COURSE

BID OPENING DATE – OCTOBER 6, 2020

The specifications of this bid have been changed as follows:

Page A1 has been added to the specifications.

These new pages shall be attached to and become part of the specifications.

Failure to acknowledge this addendum on the Addendum Acknowledgment form with your bid submission will result in the rejection of your bid.

O.C. DEPARTMENT OF PURCHASE

JENNIFER L. BOWENS
Purchasing Agent



SPECIAL ASSISTANCE/ACCOMMODATIONS available, please call (732) 929-2101.



ADDENDUM NO. 1

September 25, 2020

Bid Title: CULVERT AND CART PATH REPAIR AT ATLANTIS GOLF COURSE

Bid Opening: October 6, 2020 11:00 AM

To All Concerned:

Regarding the Contract Documents associated with the Culvert and Cart Path Repair at Atlantis Golf Course, prepared by SUBURBAN CONSULTING ENGINEERS, INC. (SCE):

CONCERNING QUESTIONS SUBMITTED CONCERNING THE PLANS AND TECHNICAL SPECIFICATIONS:

1. *Question: Specs state the irrigation ponds must remain in working order during construction. During the site visit it was mentioned the irrigation system would be shut down during construction. Which should we follow?*

Answer: The irrigation system that would be shut down that was referred to at the pre-bid meeting is the line that feeds the irrigation heads in the lawn areas. The ponds must remain in working order and the contractor must provide a means to allow the natural flow of water through the ponds.

2. *Question: Is there a specific seed mixture to be used?*

Answer: Please refer to the Permanent Vegetative Mixtures, Planting Rates and Planting Dates Table in Section 4, Standard For Permanent Vegetative Cover For Soil Stabilization, of the Standards for Soil Erosion and Sediment Control in New Jersey, Seed Mixture No. 13 as noted below.

<u>Mixture</u>	<u>Planting Rate (lbs./1000 square feet)</u>
Hard Fescue and/or Chewing Fescue and/or	
Strong Creeping Red Fescue	4
Perennial Ryegrass	1
Kentucky Bluegrass	1

3. *Question: Will turbidity barriers be required during construction?*

Answer: It is the contractor's responsibility to determine means and methods of construction. Turbidity barriers may be used as part of the overall method of maintaining the flow between the ponds.

4. *Question: During the site visit it was mentioned the extent of asphalt stopped at the roadway just before Country Club Blvd. The plans show asphalt roughly 20' before the pointed mark during the site visit. Which should we follow?*

Answer: Please follow the limits shown on the plans.

Bidders are advised that submissions must include an acknowledgement of receipt of addenda found on the Addendum Acknowledgement form in the Contract Documents. **Failure to do so will be cause for rejection of bid.**

END OF ADDENDUM NO. 1